

ESTIMATE FOR THE REPAIRING WORK
OF OLD & DAMAGED CHAJJA OF SCHOOL BUILDING AT PVSS DAV
PUBLIC SCHOOL JHUMRI TELAIYA, KODERMA JHARKHAND

| Sl.No | Description of items | Quantity | Rate | Amount Rs |
|-------|--|--------------------|------|--------------|
| 1 | Providing 12 mm thick cement plaster (1:6) over walls all as per building specification. 10'0''x4'6'' x 91 pc = 4095 sft 6'0''x3'6'' x 4 pc= 84 sft 19'0''x3'6'' x 4 pc =266 sft 9'0''x3'6''x 6 pc=189 sft 13'0''x3'6''x 40 pc =1820 sft 19'0''x3'6''x 3 pc=199.5 sft ----- 6653.5 sft Add 5% unseen area 332.67 sft ----- 6986.17 sft | 649.27 m2 | | |
| 2 | Dismantling old & damage plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 meter lead. 50% of Area vide item 1 Or, 50% of 649.27 m2 = 324.63 m2 | 324.63 m2 | | |
| 3 | Providing and fixing scaffolding on the exterior side upto seven floor height and maintaining it in a serviceable condition for the required duration as approved and removing it there after. Area vide item 1 = 649.27 m2 | 649.27 m2 | | |
| | | TOTAL | | |
| | G.S.T % | | | |
| | | GRAND TOTAL | | |